



MACSONS JOB PROFILE

Contact: Andrew Dunnum ■ Mb: (757) 310-1407 / Ph: (757) 624-1733 / Fx: (757) 624-5356 ■ adunnum@macsons.com

Heavy demolition of Hog Island Coast Guard Station



All heavy equipment had to be transported by barge to the Island; then rubble removed.



BEFORE



AFTER

Heavy Demolition

Details:

- Owner: The Nature Conservatory
- General Contractor: NA
- Project Name: Demolition Hog Island CG Station
- Location: Nassawadox, VA

Description:

Project included asbestos abatement and disposal, heavy demolition of building, and waste removal from off the Island. Manifested loads required Macsons to provide equipment, materials, tools, machinery, vessels, vehicles, labor and supervision necessary for transportation, demolition, site management, removal and disposition of debris and dock piling, and back filling work. All above ground plumbing was removed; septic tanks filled. A fresh water cistern under the boathouse was demolished. Two 1,000 gallon diesel fuel tanks were emptied in order to be classified as demolition debris. Steel rails and rail trolley in front of the station, as well as an old diesel generator lying by the boathouse, were removed and disposed of on the mainland. Macsons coordinated tug boats, floating cranes, barges, to execute the island demolition.



DEMOLITION & ENVIRONMENTAL SERVICES

Corporate Offices, Norfolk VA ■ Recycling Yard, Chesapeake VA